

NOTE: REMOVED REFERENCES TO SPECIFIC HOMEOWNERS

SITE ID	HWG	RANK	WBODY	OWNER	DESCRIPTION OF PROBLEM	RECOMMENDATIONS	TSS (lbs./yr)	TP (lbs./yr)	TN (lbs./yr)	Est. Low Cost	Est. High Cost
GL-01	Y	1	Gregg L	Town	Road surface, shoulder, and ditch erosion	Grading and stabilization of road surface.	1,175	2.5	7.9	\$15,000	\$25,000
GL-07		2	Gregg L	Private	181 Gregg Lake Rd; private beach, 2 truck	Minimize area of private sandy beach with	3,960	1.7	3.4	\$10,000	\$20,000
GL-12		2	Gregg L	Town/Priv.	Private beach off White Birch Point Rd, rur	Minimize area of private sandy beach with	741	1.6	7.7	\$10,000	\$30,000
GL-23		2	Gregg L	Private	104 Gregg Lake Rd, private sandy beach, r	Minimize area of private sandy beach with	2,571	1.1	2.2	\$15,000	\$30,000
GL-08		2	Gregg L	Private	171 Gregg Lake Rd; private beach, minima	Minimize area of private sandy beach with	1,571	0.7	1.3	\$10,000	\$20,000
GL-18		2	Gregg L	Private	Harbor Camp Beach, beach sand erosion i	Decrease the size of the beach area. Imprc	465	0.8	5.6	\$20,000	\$30,000
GL-17		2	Gregg L	Private	140 Brimstone Corner Rd, eroding access	Regrade and armor path surface with crus	500	0.2	0.4	\$5,000	\$10,000
GL-20		2	Gregg L	Private	197 Gregg Lake Rd, private beach access t	Minimize area of private sandy beach with	220	0.1	0.2	\$10,000	\$20,000
GL-09	Y	3	Gregg L	Town/Priv.	Runoff from S Holt Hill Rd carries sedimen	Minimize area of private sandy beach with	564	1.1	2.5	\$30,000	\$40,000
GL-10	Y	4	Gregg L	Private	2 Gregg Lake Dr, runoff from hilly road car	Armor road shoulder with vegetation and	291	0.7	2.2	\$10,000	\$30,000
GL-11	Y	5	Gregg L	Town	White Birch Point Rd to dam outlet; multi	Regrade unpaved road surface, armor roa	630	1.2	3.6	\$30,000	\$50,000
GL-19	Y	6	Gregg L	Town	Public beach and parking lot off Gregg La	Stabilize and armor shoreline with shrubby	74	1.3	5.5	\$75,000	\$100,000
GL-05	Y	6	Gregg L	Town	Boat launch to Gregg Lake off Gregg Lake	Regrade access area with stable material.	133	0.5	1.8	\$30,000	\$50,000
GL-14		7	Gregg L	Town	High lake levels causing undercut and ero	Regrade and stabilize/build-up road shoul	5,000	2.1	4.3	\$50,000	\$75,000
GL-04		7	Gregg L	Town	Minimal road shoulder and buffer between	Add to the vegetated buffer along both si	4,000	1.7	3.4	\$50,000	\$75,000
GL-03	Y	7	Gregg L	Town	Gregg Lake Rd bridge at inlet stream with	Add to the vegetated buffer along both si	1,500	0.6	1.3	\$20,000	\$30,000
GL-02		7	Gregg L	Town	Large dirt pull-off area at the intersection	Decrease the size of the pull-off area and	132	0.3	0.6	\$15,000	\$30,000
GL-15		7	Gregg L	Town	Winter oil slick on lake water near 189 Gre	Regrade and stabilize/build-up road shoul	200	0.1	0.2	\$10,000	\$20,000
GL-13		8	Wetland	Private	Timber harvest off Gregg Lake Rd across fi	Replant vegetation. Install vegetated swal	379	0.8	4.4	\$15,000	\$25,000
GL-24		9	Gregg L	Private	Gregg Lake Dr, minimal buffer along lake	Encourage "no-mow" practices along the	210	0.5	2.0	\$15,000	\$25,000
GL-28		10	Indirect	Town	55/58 Brimstone Corner Rd, road shoulder	Stabilize road shoulder and ditches. Armo	529	0.6	1.5	\$10,000	\$20,000
GL-27		10	Indirect	Town	Brimstone Corner Rd, road shoulder and d	Stabilize road shoulder and ditches. Armo	526	0.6	1.4	\$10,000	\$20,000
GL-29	Y	10	Indirect	Town	North of 60 Brimstone Corner Rd, road sh	Stabilize road shoulder and ditches. Armo	524	0.6	1.4	\$10,000	\$20,000
GL-30		10	Indirect	Town	85 Brimstone Corner Rd, road surface and	Reshape and re-crown road, stabilize road	785	1.0	2.1	\$15,000	\$30,000
GL-31		10	Indirect	Town	93 Brimstone Corner Rd, unstable culvert	Stabilize road shoulder and ditches. Armo	313	0.4	0.8	\$10,000	\$20,000
GL-25			Wetland	Town/Priv.	Craig Rd intersection with Hattie Brown Rc	Regrade road surface and shoulder. Plant	92	0.2	0.4	\$5,000	\$10,000
GL-16			Gregg L	Town	Culvert at 180 Gregg Lake Rd (several oth	Armor ditches with vegetation and check	18	0.2	0.1	\$10,000	\$20,000
GL-21			Indirect	Town	S Holt Hill Rd, road surface and ditch erosi	Clean out and armor ditches with vegetati	938	0.4	0.8	\$10,000	\$20,000
GL-22			Indirect	Town	S Holt Hill Rd, steep road shoulder unstab	Stabilize road shoulder.	100	0.2	0.6	\$5,000	\$10,000
GL-06			Trib. to Gre	Town	Small wooden bridge on Craig Rd over inl	Armor road shoulder with vegetation and	62	0.1	0.3	\$10,000	\$20,000